

NOTICE

Reconstruction of a Hampshire St and Oxford Rd

The DPW-Highway Division has scheduled the reconstruction of Hampshire St from West St to the Foxboro line and Oxford Rd to start on August 17th 2016. (The contractor provided us with a short notice but the road will remain open during milling operations).

This work involves several phases as indicated below, please be aware that the dates given are approximate and subject to change based upon weather and individual contractor schedules.

Phase 1 – Milling, begins on August 17th and is expected to take three days. This phase involves milling approximately 2” of the existing asphalt surface.

Phase 2 – Full depth repairs of potholed areas.. This will be done as needed immediately following milling.

Phase 3- Adjust Castings – This phase involves the raising of castings in preparation for final paving.

Phase 4 – Installation of Stress Absorbing Membrane Interlayer (SAMI), this is also known as a rubber chipseal- Tentatively scheduled for Sept. 7th.

Phase 5- Final Paving – Tentatively scheduled for mid to late September.

Please note that the schedule for Phase 3 & 4 are tentative and subject to weather and contractor delays.

Please be aware that upon final paving, the road will have a five (5) year “no dig” moratorium.

We apologize for any inconvenience this may cause, however this work is necessary in order to maintain the goals of Mansfield’s pavement preservation plan. Please be aware that the construction schedule is subject to change depending on weather conditions. **If anyone is considering adding or upgrading water, sewer or gas services, please schedule it immediately with the appropriate utility and also notify the DPW.** If you have any questions please contact the DPW Office at 508-261-7335 or mcook@mansfieldma.com. Please refer to www.mansfieldma.com for updates.